



# COLLEGE OF ENGINEERING, SHIVAJINAGAR, PUNE 411 005

Off.: + 91-20-25507203.

Fax + 91-20-25507299.

REF NO: COEP/AMD/BGB/ Frozen Semens Lab/2022/ B-1081

Date:05/03/2022

## Call for Quotation

On behalf of Animal Husbandry Dept, ( विभागीय व्यवस्थापक , गोठित रेत प्रयोगशाळा खडकी पुणे ) Govt. of Maharashtra, Quotations in sealed envelope are invited from reputed vendors from 05 April 2022 to 11 April 2022 on office hour for **Addition to laboratory at Frozen Semen's Laboratory Mula road, Khadki, Pune.** The blank quotation form can be downloaded from the website of COEP. The demand draft of Rs. 500/- should be attached while submission the quotation offers. The quotation shall be submitted to the office of College of Engineering Pune, Inward section on or before 11/03/2022. Quotations will be opened on 12 April 2022 at 11.30 am. Envelope containing the quotation should be addressed to the "Prof. B. G. Birajdar, Project Consultant, College of Engineering Pune, and should have title on quotation envelope "Civil Wotk -**Addition to laboratory at Frozen Semen's Laboratory Mula road, Khadki, Pune.**". and Reference No. COEPAMD/Frozen Semens Lab/2022/ 2758 Date: 05/03/2022 written on it.

Other Terms and conditions of Quotation:-

1. Work duration would be 15 days.
2. The rate quoted is inclusive of Transport, VAT, Service Tax & other Taxes.
3. TDS will deduct at source and certificate to that effect will be given.
4. The work should be completed before the schedule time frame, failure to do so will be liable to pay penalty of Rs. 500/- per day subject to maximum 5% of total value.

B. G. Birajdar  
Professor, Applied Mechanics  
College of Engineering,  
Pune -411 005

**Quotation for "Addition to laboratory at Frozen Semen's Laboratory Mula road, Khadki, Pune."**

REF NO: COEP/AMD/BGB/Frozen Semens Lab/2022/ B-1081

Date:05/03/2022

To,  
The Professor,  
Civil Engg Deptt  
College of Engineering,  
Pune – 411005

Sub: "Quotation Civil Works -for **Addition to laboratory at Frozen Semen's Laboratory Mula road, Khadki, Pune**".

Ref: your reference No. COEP/AMD/BGB/ Frozen Semens Lab/2022/ B-1081 date:05/03/2022.

Sir,

I/We have pleasure in submitting herewith our quotation for the above-mentioned works, duly completed in all respects. The rates quoted in the tender will be valid for six months from the date of opening of the quotation.

Item No	SSR No.	Description	Unit	Quantity	Rate	Amount in Rs
1	46.19	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts, complete. Spec. No.: As directed by Engineer in charge	Sqm	11.84		
2	46.40	Removing urinal pan s or wash hand basin s with frame including disconnecting the sanitary and water supply connections, removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc complete SSR NO.46.40	No.	2.00		
3	46.13	Removing rich mix cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.	Cum	1.92		
4	46.41	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring	No.	1.00		

		and bed concrete around pan removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc. carefully and throwing out there fusel outside etc. complete. SSR NO.46.41				
5	33.67	Providing and laying Antiskid Ceramic tiles of approved quality of size 30 cm x 30 cm and confirming to IS 15622-2006 (Group-B IIA) for antiskid flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with cement slurry cleaning curing etc. complete.	Sqm	1.26		
6	33.26	Providing and laying ceramic tiles having size 30 cm. x 60 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	Sqm	14.55		
7	36.11	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.	Sqm	3.60		
8	24.01	Providing and laying in situ cement concrete M 10 of trap /granite / quartzite / gneiss metal for foundation and bedding including dewatering, form work , compacting, roughening them if special finish is to be provided, finishing if required and curing with fully automatic microprocessor based PLC with SCADA enabled concrete Batch mix plant (Pan mixer) etc. complete.	Cum	2.45		

9	39.28	Providing and fixing sheet glass of 24 oz. for all size including putty etc. complete	Sqm	21.60		
10	46.46	Replacement of damaged aluminum Butt Hinges of 125mm of approved quality and make to door shutter including removing existing the same in original position making proper adjustment for smooth operation etc. complete as per sample approved by Engineer in-charge.	No.	8.00		
11	46.47	Replacement of damaged Mortise Lock of approved quality and make to door shutter including Removing and Refixing with Necessary screw, making proper adjustment for smooth operation etc. complete as per sample approved by Engineer in-chareg.	No.	5.00		
12	46.51	Replacement of damaged Aluminum Handle 125mm of approved quality and make to door / window shutter including removing existing the same in original position making proper adjustment for smooth operation etc. complete as per sample approved by Engineer in-charge.	No.	5.00		
13	39.53b	Providing and fixing in position aluminum fixed window fully glazed of any size as per detailed drawing and as directed by Engineer in-charge with all necessary aluminum sections including necessary fixtures and fastening such as 5 mm thick clear float glass etc. complete.	Sqm	0.96		
14	42.35	Providing and fixing orissa type colour glazed earthenware 625x450mm. w.c .pan including trap, C.I .soil and vent pipe upto the out side face of wall including 100mm. dia. C.I. plug, bend ,15mm. thick 10 liter PVC flushing cistern with all necessary pipe connection etc. complete.	No.	1.00		

15	41.63	Providing and fixing White glazed earthenware Wash Hand Basin of 55x40 cm size including cold water pillar taps, brackets, rubber plugs and brass chain, stop tap, chromium plate bottle trap and necessary pipe connections including UPAC waste pipe and trap upto the outside face of the wall, making good the damaged surface, testing etc. complete.	No.	2.00		
16	41.57	Providing and fixing White Glazed Earthenware full stall type Urinal with P.V.C. flushing cistern of 5 liters capacity with fitting, inlet pipe and stoptap, brackets for fixing the cistern ,32mm dia.P.V.C flush pipe with fitting sand flushing arrangement including lead soil pipe, lead trap, soil pipe connection up to the outside face of the wall	No.	1.00		
17	46.55	Manually clearing by removing the chocks from Nahni Trap ,Gully Trap, Wash basin unit, Sink and WC with the help of required tools for proper functioning the same etc. complete.	No.	10.00		
18	42.67	Providing and fixing 10 cm PVC nahani trap with grating etc. complete.	No	2.00		
19	42.52	Providing and fixing 100mm destabilizer pipe / P.V.C. Solvent /waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. Complete.	Rmt	20.00		
20	42.28	Providing, laying and fixing P.V.C. pipe of 110 mm. dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Rmt	15.00		

21	31.09	Providing and applying waterproofing treatment using acrylic polymer modified cement based waterproofing coating with fiber glass mesh mixing at the rate of powder to liquid (2:1) by weight covering 9 to 10 Square Meter/Kilogram with two coats using approved chemicals form as only and concrete surface by brush covering 7 years guarantee on Stamp Papers etc. complete.	Sqm	132.60		
22	41.18	Providing and laying in trenches 15mm dia. medium grade having embossed as ISI Mark galvanized iron pipes of 1.25 Kilogram/meter necessary fitting remaking good the demolished portion with filling trenches and with primer of anti-corrosive oil paint ,2 coats Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Rmt	75.00		
23	41.19	Providing and laying in trenches 20mm dia. medium grade having embossed as ISI Mark galvanized iron pipes of 1.25 Kilogram/meter necessary fitting remaking good the demolished portion with filling trenches and with primer of anti-corrosive oil paint ,2 coats Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Rmt	15.00		
24	41.20	Providing and laying in trenches 25mm dia. medium grade having embossed as ISI Mark galvanized iron pipes of 1.25 Kilogram/meter necessary fitting remaking good the demolished portion with filling trenches and with primer of anti-corrosive oil paint ,2 coats Including removing existing pipe line if necessary and conveying and stacking the same in PWD	Rmt	10.00		

		chowky or as directed etc. complete.				
25	42.02	Providing and fixing 15cmx10cm salt glazed stone ware gully trap in cement concrete 1:4:8 outside the building including cast iron grating in the sink, connecting glazed stone ware pipe, brick masonry chamber with cast iron lid and cast iron grating for the gully trap.	No.	1.00		
26	41.40	Providing and fixing 15mm dia. Screw down bib/stop tap of brass including necessary socket union nut complete.	No.	8.00		
27	42.84	Providing and fixing C.P.sink cock with raised J" shaped swinging casted spout of approved make including necessary sockets/ union nut etc. complete."	No.	8.00		
28	42.37	Providing and fixing 15mm.dia Ball cock medium type with PVC float including sockets and necessary fittings and tested as per municipal requirement etc. complete.	No.	2.00		
29	42.53	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of high density polythylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	Lit	1,000.00		
30		Metalic pass box should be designed to allow material transfer through controlled movement without much personal movement to minimize man/ material movement and cross contamination between different classified areas complete as required including all accessories as per technical specification.	No.	1.00		

31	51.51	Providing and fixing 4 legged Lab stool, Legs made of 16 Guage 45MM Outer dimension MS Pipe, Duly painted, With a 304 Grade Stainless steel 12 inch wide seat with a 1 inch collar, Height adjustment via as crew. as per design and drawing and instructions of Engineer in charge.	No.	2.00		
<b>Total Amount in Rs</b>						
<b>Add GST .....% Rs</b>						
<b>Final Amount in Rs</b>						
<b>Say Rs</b>						

I/ We agree to execute the works in accordance with the approved drawing and technical specifications for a total contract price of Rs..... (Rs...  
.....) (Amount in fig.)  
{Amount in words) Including all Taxes.

**Seal of company**

**Signature of bidder**

Encl: 1) Registration of firm,  
2) Experience certificate  
3) Last three-year income tax returns certificate.  
4) Registration of GST